



ELEVATIONS

A horizontal sheeting rail must be fixed to the outside of the scaffold, on singles, at the **top** and **bottom** of the sheeting requirement.

Where a horizontal join between sheets is required, (normally every 6 metres or 3 lifts), install two sheeting rails, approximately 20cm apart.

A horizontal sheeting rail installed around the scaffold structure on every lift will hold the Tufcoat scaffold sheeting away from scaffold fittings and reduce the risk of damage to the sheeting (optional).

A scaffolder must be present at the beginning of the project to make any necessary amendments and should be contactable

throughout the projects duration.



WEATHER

The installation of Tufcoat sheeting may be **delayed by wind and heavy rain**.


The installation should not be started unless it is certain that the forecast weather will allow any installed sheets to be welded and shrunk before the installers leave site. If sheets are left un-shrunk they may cause any welded joints and sheets to be damaged.


For sheeting sides, **rain may cause problems with the appearance** of the sheeting following the heat shrink process and with the quality of any joins between sheets.

Roofs should not be attempted if it is raining or if rain is expected before the sheet can be installed and heat shrunk tight.





TUFCOAT SHRINK-WRAP SETUP GUIDE FOR TEMPORARY ROOFS







Roof sheeting rails must be installed beneath the perpendicular boards 20cm away from boards to secure sheets.







A **run of 3 boards** should be installed around the perimeter of the roof, please leave the toe board off to ensure that the sheeting runs smoothly over the edge.



Roof access should be via ladder and safety access gate, at the side of the roof. Where access is provided through the roof there is a risk of leaks in the completed job.

Upon completion, the Tufcoat team leader will complete a handover document which will be given to your nominated on-site representative describing the work that has been carried out.



















